

Activity name	Location /site description	Problem / Opportunity	Brief scope description / proposed treatment	Type of intervention	2018/19	2019/20	2020/21
Intersection improvements, Ashburton	Cass St / Tancred St: Improve safety at Ped Xing a	Improve pedestrian crossing facility at intersecti	Improve design or location of current pedestrian	Walking improvements (incl. pedestrian, pram or	-	-	Draft
Intersection Improvements, Tinwald	Maronan Rd/Melcombe St/Henderson Rd: Upgra	Poor sight lines, priorities unclear and proximity	Strengthening (AC) and reshaping (for drainage).	Minor geometric improvements	-	Completed	-
Intersection Improvements, Ashburton	Chalmers Ave/Wellington St/Havelock St, New Tr	Priority unclear for road users.	New priority, lane removal and signage options r	Signage / delineation / pavement marking	-	-	Draft
Melcombe St Cycle Access	Rail underpass on Melcombe to cater for cyclists	Conflict between cyclists, pedestrians and motor	Marking and signs changed and raised path instal	Cycling improvements (incl. paths; lanes; marking	-	-	Draft
Road realignment, Rural	Realign Line Road to remove bend and crest curv	Hidden curve and intersection. High HCV use as l	Remove danger caused by vertical and horizontal	Intersection improvements (inc. signalisation / rd	-	-	Construction
Bridge Replacement - Arundel Rakaia Gorge Road	Replace RDR bridge #232 on Arundel Rakaia Gorg	Rangitata Diversion Race bridge at end of life and	Replace bridge to carry HPMV loads	Replacement bridges and structures	-	-	Construction
Bridge Replacement - Arundel Rakaia Gorge Road	Replace RDR bridge #233 on Arundel Rakaia Gorg	Rangitata Diversion Race bridge at end of life and	Replace bridge to carry HPMV loads	Replacement bridges and structures	-	-	Construction
Bridge Replacement - Arundel Rakaia Gorge Road	Replace RDR bridge #234 on Arundel Rakaia Gorg	Rangitata Diversion Race bridge at end of life and	Replace bridge to carry HPMV loads	Replacement bridges and structures	-	-	Construction
School Zone Improvements	Improve overall safety outside schools in relation	Safety concerns identified outside school by NZT	Ensure overall safety outside schools	Signage / delineation / pavement marking	-	-	-
Sealing at intersections, Rural sites	Improve safety from braking and detritus. Sites t	Remove dangerous issue of inefficient braking su	Ensure seal back at intersections adjoin sealed ro	Intersection improvements (inc. signalisation / rd	Construction		
Sealing at bridge approaches	Approaches to bridges on unsealed roads	Ensure vehicles are able to brake and steer efficie	Seal approaches to bridges on unsealed roads to	Surface treatment (safety)	Completed	-	-
Installation of replacement streetlights	Where coordinated with Electricity Ashburton	Remove power poles to be replaced with frangib	Installation of streetlight poles where power pole	Clear zone improvements	Construction		
New streetlighting	New Street lights in Ashburton, rural towns, rural	Improved street lighting to identify intersections	Install new streetlights where sites are identified	Lighting improvements	Construction		
Stock underpass funding, Rural	District wide locations	Part funding of stock underpass installations	Assist farmers with part funding of Stock Underp	Stock underpasses	Construction if required		
Delineation & Signage Improvements	Primary Collector Roads - intersections	A number of recent fatal crashes at intersections	Replace Give Way with Stop, install advance warr	Signage / delineation / pavement marking	Completed	-	Draft
Seal widening	Thompsons Track RP 4250-5360 and 35000-3618	required due to increased HCV and tourist volume	Widening of road width and strengthening of sho	Seal widening	-	-	Draft
Seal widening	Thompsons Track RP 20635-21500 and 22250-24	required due to increased HCV and tourist volume	Widening of road width and strengthening of sho	Seal widening	-	-	Draft
Seal widening	Seafield Rd RP 11818-15812 (existing seal width	Quantity of maintenance required due to increas	Widening of road width and strengthening of sho	Seal widening	-	-	Draft
Railway crossing road/rail improvements	Various sites	Kiwirail improvement programme requires adjac	Pavement and surfacing renewals/repair to resha	Minor geometric improvements	-	-	Draft
Speed Threshold Improvement	Fairfield Road West RP 705 (western access to Fa	Fairton is a through-route for multiple HCV destir	Installation of central island, seal widening, large	Traffic calming	Completed	-	-
Drainage Improvements	District-wide	New soakpits, sumps, culverts as required due to	Installation of appropriate drainage asset to cour	Drainage (incl. kerb and channel)	Construction		
Major Accessways - Sealing	District-wide	Rural accesses on sealed roads typically connect	Sealing of Major accessways (accesses for HCVs a	Surface treatment (safety)	Construction		
Minor Accessways - Sealing	District-wide	Rural accesses on sealed roads typically connect	Sealing of Minor accessways (accesses to houses,	Surface treatment (safety)	Construction		
New Footpaths - Ashburton	Tarbottons Rd [ASH]	Pedestrian safety and community access.	Install new footpaths.	Walking improvements (incl. pedestrian, pram or	Completed	-	-
New Footpaths - Methven	Methven Chertsey Rd [MTH]	Pedestrian safety and community access.	Install new footpaths.	Walking improvements (incl. pedestrian, pram or	-	Completed	-
New Footpaths - Rakaia	Normanby St West [RAK]	Pedestrian safety and community access.	Install new footpaths.	Walking improvements (incl. pedestrian, pram or	Completed	-	-
New Footpaths - Rural	Patton St Mt Somers[RRL] and Robert St Hinds [R	Pedestrian safety and community access.	Install new footpaths.	Walking improvements (incl. pedestrian, pram or	-	Construction	
New Kerb & Channel - Ashburton	Ashburton	New kerb & channel	Install new kerb and channel.	Drainage (incl. kerb and channel)	Completed	-	-
New Kerb & Channel - Ashburton	Tarbottons Rd	Gap in kerb and channel due to subdivision work	Install new kerb and channel.	Drainage (incl. kerb and channel)	-	Completed	-
New Kerb & Channel - Methven	Methven Chertsey Rd	Extend footpath and kerb and channel to cemete	Install new kerb and channel.	Drainage (incl. kerb and channel)	-	Completed	-
New Kerb & Channel - Rural	Pattons Rd (Mt Somers), Robert St (Hinds)	These sites were undeveloped when kerb and ch	Install new kerb and channel.	Drainage (incl. kerb and channel)	-	Construction	
Bridge Guardrail Safety Improvement	Maronan Bridge (No. 72 on Maronan Road at RP	Two fatal crashes (Sep 2015 and Feb 2019 - both	The existing kerb and guardrail will be replaced t	Kerb and guardrail redesign/upgrade.	-	-	Construction
Resilience Improvements	Winslow Road Sunshine Bridge	Washouts on gravel approach occurring frequent	New gabion baskets installed on approach.	Resilience improvements	-	Completed	
New Footpaths - Ashburton CBD	Ashburton CBD	Work associated with the CBD project.	Various as described in CBD project works.	Walking improvements (incl. pedestrian, pram or	-	-	Construction
New Kerb & Channel - Ashburton CBD	Ashburton CBD	Work associated with the CBD project.	Various as described in CBD project works.	Drainage (incl. kerb and channel)	-	-	Construction